

PSC NO: 3 - WATER

LEAF: 13

COMPANY: HERITAGE HILLS WATER-WORKS CORPORATION

REVISION: 0

INITIAL EFFECTIVE DATE: November 30, 2010

SUPERSEDING REVISION:

**B. Location of Meters**

- (1) The Customer shall provide a place acceptable to the Company, for the location of the meter.
- (2) Meters should be installed inside buildings, unless otherwise required or agreed to by the Company. They are usually located in basements and should be placed in a clean, dry, safe place at or near the front wall, as close as possible to the point of entrance of the connecting pipe.
- (3) Meters should be supported firmly, not less than 12 inches nor more than 36 inches above the floor level and should be readily accessible at all reasonable times for inspection, reading or changing by employees of the Company.
- (4) Where it is necessary to set the meter outside the building, it shall be installed, at the expense of the customer, in a pit which is water-tight and frost-proof. The cover of the pit shall be fastened with a convenient locking device. Where the distance from the property line to the front wall of the building is greater than 75 feet, the Company may require that the meter be set at or near the property line. If the pit is to be located upon property not owned or controlled by the customer, written consent of the owner shall be first obtained.

Issued By: Henry Paparazzo, President, Southbury, Connecticut 06488