Received: 10/03/2006
Status: CANCELLED
Effective Date: 01/01/2008

Form of Facilities Construction and Reimbursement Agreement
For Electric Generation
EXHIBIT B – Continued

VI. Above Ground Pipe Requirements

a. All piping that will be above grade must be of low temperature material. Pipe and fittings must meet Charpy V-Notch values of 20 ft-lbs @ 0 F.

b. Pipe materials shall be: for 2 1/2" through 10": ASTM 333 Grade 6, standard wall; for pipe 12" and larger: API 5L X-42 PSL-2 standard wall.

VII. Records

a. A copy of all Certified Material Test reports for all pipe, fittings and welding rods must be provided to KeySpan before gassing in.

b. A professional engineer stamped letter shall be submitted to KeySpan which identifies that the gas piping has been designed, tested, and installed to all applicable codes and standards.

c. A copy of the as-built mechanical drawings from outlet of meter to inlet of compressor building shall be provided.

Cancelled by supplement No. 44 effective 01/01/2008
Suspended to 01/01/2008 by order in Case 06-G-1185. See Supplement No. 43. Th e supplement filing date was 08/30/2007
Suspended to 09/03/2007 by order in Case 06-G-1185. See Supplement No. 42. Th e supplement filing date was 02/27/2007
Suspended to 03/03/2007 by order in Case 06-G-1185. See Supplement No. 41. Th e supplement filing date was 11/01/2006